



Engineering Division

TOWN OF ARLINGTON  
Department of Public Works  
51 Grove Street  
Arlington, Massachusetts 02476  
Office (781) 316-3320 Fax (781) 316-3281

April 8, 2022

## **Bid 22-16 Curb and Sidewalk Installation Project**

### **Addendum #1 Summary of Additional Information**

- 1. Page 9 of the contract, Bid Sheet Item #14 has the wrong unit displayed. Item 14 - Install 4" Concrete Sidewalks unit should display SY (Square Yards).**

ITEM	ESTIMATED QUANTITY	DESCRIPTION	UNIT
14	715	INSTALL 4" CONCRETE SW	SY (Square Yards)

#### **Item 14: Install 4" Concrete Sidewalks**

INSTALL 4" CONCRETE SIDEWALK: This work shall consist of the necessary work associated with the proper base preparation, grading, formwork, adjusting water gate valve boxes, service boxes including gas, water boxes etc, pouring of concrete 4" in depth outside the transition area, concrete finishing, stripping and removal of forms and spray application of a water-emulsified resin based concrete curing compound. Payment shall be made by the Square Yard (SY).

- 2. The following sections have been added/updated on the contract documents to reflect the changes made to the bid sheet as displayed above.**

- Page 9 – Updated Bid Sheet



TOWN OF ARLINGTON  
DEPARTMENT OF PUBLIC WORKS  
Engineering Division  
Arlington, Massachusetts 02476  
Ph. 781-316-3320 Fax 781-316-3281

**Project Title: Bid # 22-16 Curb and Sidewalk Installation Project**

ITEM	#	QUANTITY	UNIT	DESCRIPTION	UNIT PRICE	AMOUNT
1	120	20	CY	UNCLASSIFIED EXCAVATION		
2	151	276	CY	GRAVEL BORROW - RAMP, SIDEWALK & ROADWAY		
3	170	800	SY	FINE GRADE AND COMPACT		
4	220.1.2	2	VF	STRUCTURE ADJUSTED		
5	220.2	2	EA	STRUCTURE REBUILT		
6	484	3400	LF	SAWCUTTING PAVEMENT AND CONCRETE		
7	504	3000	LF	FURNISH AND INSTALL 6" STRAIGHT GRANITE CURB, TYPE VA-4		
8	504.1	100	LF	FURNISH AND INSTALL 6" CURVED GRANITE CURB, TYPE VA-4		
9	511.1	100	LF	FURNISH & INSTALL STRAIGHT 4" GRANITE CURB		
10	516	136	EA	FURNISH & INSTALL 2FT RADIUS GRANITE RETURN STONE		
11	580	400	LF	GRANITE CURB, REMOVE & RESET		
12	582	20	EA	REMOVE AND RESET 2FT RADIUS GRANITE RETURN STONE		
13	594	200	LF	CURB STONE/COBBLE EDGES REMOVED AND DISCARDED		
14	701	715	SY	INSTALL 4" CONCRETE SIDEWALK		
15	701.1	907	SY	INSTALL 6" CONCRETE DRIVEWAY		
16	701	40	SY	INSTALL 6" CONCRETE CURB RAMP WITH DETECTABLE PANEL		
17	702	40	TN	HOT MIX ASPHALT SIDE WALK SURFACE		
18	702	20	SY	EXCAVATE AND DISPOSE EXISTING SIDEWALK/DRIVEWAY		
19	751	40	CY	PLANTABLE SOIL LOAM BORROW		
20	765	600	SY	SEEDING & ROLLING		
21	874	2	EA	REMOVE & STACK STREET SIGNS		
					Total:	

**Prices must be in Writing and Figures**

TOTAL BID PRICE IN WORDS : \_\_\_\_\_

FIRM NAME : \_\_\_\_\_

NAME PRINCIPAL: \_\_\_\_\_

ADDRESS: \_\_\_\_\_

AUTHORIZED SIGNATURE: \_\_\_\_\_

DATE: \_\_\_\_\_

CONTACT NAME: \_\_\_\_\_